

ADDENDUM #1

TO

SPECIFICATION AND CONTRACT DOCUMENTS

August 3, 2016

TO: ALL PLAN HOLDERS

FOR: ITB-023-2016
LIFT STATION 160 – RENOVATION

The purpose of addendum #1 is to answer questions received to date.

Contractor must acknowledge receipt of all addenda with bid proposal on the form provided herein.

- 1) What is the expected bypass flow for the temporary bypass pumping?

Please see attachment which is the “Derived Flow Report” for Lift Station 160 from April 2, 2016 through May 2, 2016.

No. 1 Dated _____

Signature: _____

THIS FORM MUST BE INCLUDED WITH BID PROPOSAL

Derived Flow Report

Report

From 00:00 04/02/16 To 00:00 05/02/16 Time Filter 00:00 - 24:00

April 02, 2016

Station Name	Station Number	Cycles	Average Inflow GPM	Avg Pump Rate GPM	Total Gallons
LS 160 Burger King	77	250	151.04	399.26	216897.81

April 03, 2016

LS 160 Burger King	77	236	114.25	445.54	163586.94
--------------------	----	-----	--------	--------	-----------

April 04, 2016

LS 160 Burger King	77	213	94.62	478.02	135702.03
--------------------	----	-----	-------	--------	-----------

April 05, 2016

LS 160 Burger King	77	216	99.44	441.81	142520.34
--------------------	----	-----	-------	--------	-----------

April 06, 2016

LS 160 Burger King	77	207	91.38	463.84	131065.38
--------------------	----	-----	-------	--------	-----------

April 07, 2016

LS 160 Burger King	77	209	94.1	451.14	135025.11
--------------------	----	-----	------	--------	-----------

April 08, 2016

LS 160 Burger King	77	223	103.21	460.82	147648.13
--------------------	----	-----	--------	--------	-----------

April 09, 2016

LS 160 Burger King	77	246	117.51	462.91	168639.39
--------------------	----	-----	--------	--------	-----------

April 10, 2016

LS 160 Burger King	77	231	105.47	483.89	151069.88
--------------------	----	-----	--------	--------	-----------

April 11, 2016

LS 160 Burger King	77	214	95.44	466.78	136695.88
--------------------	----	-----	-------	--------	-----------

April 12, 2016

LS 160 Burger King	77	208	92.11	471.73	132217.75
--------------------	----	-----	-------	--------	-----------

April 13, 2016

LS 160 Burger King	77	213	95.05	474.59	136024.91
--------------------	----	-----	-------	--------	-----------

April 14, 2016

LS 160 Burger King	77	220	99.21	463.03	142597.55
--------------------	----	-----	-------	--------	-----------

April 15, 2016

LS 160 Burger King	77	226	102.66	478.92	146987.03
--------------------	----	-----	--------	--------	-----------

April 16, 2016

LS 160 Burger King 77	228	106.66	458.8	152498.73
-----------------------	-----	--------	-------	-----------

April 17, 2016

LS 160 Burger King 77	220	99.29	473.53	142517.31
-----------------------	-----	-------	--------	-----------

April 18, 2016

LS 160 Burger King 77	202	87.19	491.76	124652.09
-----------------------	-----	-------	--------	-----------

April 19, 2016

LS 160 Burger King 77	200	87.02	476.91	124903.41
-----------------------	-----	-------	--------	-----------

April 20, 2016

LS 160 Burger King 77	201	87.73	475.62	125667.04
-----------------------	-----	-------	--------	-----------

April 21, 2016

LS 160 Burger King 77	190	82.75	464.22	118501.1
-----------------------	-----	-------	--------	----------

April 22, 2016

LS 160 Burger King 77	206	92.98	454.16	133084.91
-----------------------	-----	-------	--------	-----------

April 23, 2016

LS 160 Burger King 77	202	89.93	451.63	128879.2
-----------------------	-----	-------	--------	----------

April 24, 2016

LS 160 Burger King 77	208	93.95	437.44	134694.97
-----------------------	-----	-------	--------	-----------

April 25, 2016

LS 160 Burger King 77	186	80.55	449.59	115326.99
-----------------------	-----	-------	--------	-----------

April 26, 2016

LS 160 Burger King 77	185	79.95	450.03	114119
-----------------------	-----	-------	--------	--------

April 27, 2016

LS 160 Burger King 77	195	84.21	460.71	120868.15
-----------------------	-----	-------	--------	-----------

April 28, 2016

LS 160 Burger King 77	219	127.51	428.63	182837.16
-----------------------	-----	--------	--------	-----------

April 29, 2016

LS 160 Burger King 77	244	159.56	424.82	228482.09
-----------------------	-----	--------	--------	-----------

April 30, 2016

LS 160 Burger King 77	256	164.18	424.45	235561.41
-----------------------	-----	--------	--------	-----------

May 01, 2016

LS 160 Burger King 77	261	162.39	445.36	232413.11
-----------------------	-----	--------	--------	-----------

May 02, 2016

LS 160 Burger King 77	247	142.92	439.95	204847.44
-----------------------	-----	--------	--------	-----------

Station Name	Station Number	Cycles	Average Inflow GPM	Avg Pump Rate GPM	Total Gallons
LS 160 Burger King	77	6762	105.94387096774	456.44806451613	4706532.24

End of Report
